



December 15, 1997

Mr. Wayne Praskins
Project Manager
U.S. Environmental Protection Agency
75 Hawthorne Street (SFD-7)
San Francisco, California 94105

Re: Release of Perchlorate to Ground and Groundwater via Historic Burn Practices

Dear Wayne:

During our meeting at Region 9 on October 22, 1997, we discussed other potential responsible parties (PRPs) for the release of perchlorate ion to the ground and groundwater in the BPOU. EPA indicated that additional evidence would be required to support the BPOU Steering Committee position that perchlorate disposal practices by Day & Night resulted in soil and groundwater contamination. Day & Night, as directed and overseen by the United States, placed perchlorate on the ground and burned the compound as described in documents previously submitted to EPA.

Documents submitted to regulatory agencies establish without question that the practice of burning perchlorate in burned areas results in release of perchlorate to soil and the transport of perchlorate through soil to groundwater.

- 1. In 1992 Radian Corporation prepared a report on behalf of Lockheed Corporation for submittal to the Santa Ana Regional Water Quality Control Board regarding Lockheed's Beaumont No. 1 facility. Portions of this report are enclosed. You will note that perchlorate was found in groundwater concentrations ranging upward to 9,000 µg/l downgradient of Lockheed's burn pit area and that Radian attributes the source of the perchlorate to the burn pit.
- 2. United Technology Corporation Chemical Systems Division located in San Jose, California develops, manufactures and tests solid propellant propulsion systems. The operation uses solid rocket motors containing aluminum and ammonium perchlorate suspended in a synthetic rubber matrix. Waste propellant has historically been thermally treated at an Open Burning Facility (OBF) located on the northeastern portion of the property. This OBF is approximately 17 acres in size and contains 10 Open Burning units (OBUs). From 1963 to 1992 all wastes were burned on the ground surface.

The facility is operating under RCRA and as such is addressing environmental restoration through the RCRA Facility Investigation/Corrective Measures Study process. Documents containing information on perchlorate in soil and water include: RCRA Facility Investigation/Corrective Measures Study (June 1991 - ICF Kaiser), RCRA Facility Investigation/Corrective Measures Study Addendum (June 1993 - ICF Kaiser), and Soil and Groundwater Characterization Summary - Open Burning Facility (April 1996 - ICF Kaiser).

Prior to 1996, limited investigation and analysis of soils and groundwaters for perchlorate were performed. As of 1996 only nine soil samples from the OBF were subjected to analysis for perchlorate. Six of these nine soil samples contained concentrations of perchlorate up to 450 mg/kg with an average concentration for all nine samples of over 150 mg/kg.

Concentrations in groundwater at the OBF in 1992 to 1995 varied by well, but ranged from non-detect to $48,000 \,\mu\text{g/l}$ with an average of approximately 7,000 $\,\mu\text{g/l}$. This confirms that high concentrations in OBF soils have contributed significant concentrations of perchlorate to groundwater. This is clear evidence that the burning process does not result in complete destruction.

The DHS web page contains information that concentrations of perchlorate up to $281,000 \mu g/l$ have been detected in groundwater at the facility. We expect that additional investigations are underway but have not seen any data collected in 1997.

The information referenced above clearly demonstrates that open burning of perchlorate on ground surfaces results in perchlorate entering the ground and groundwater. Since Aerojet followed the same general procedures for perchlorate burning at its Azusa facilities as did Day & Night, if EPA concludes that Day & Night did not contribute perchlorate to the groundwater, then Aerojet must be absolved of responsibility regarding perchlorate investigation and/or remediation, especially as to perchlorate furthest in distance and time from the presumed, but as yet undefined, upper end of the perchlorate plume.

On a related matter during the October 28, 1997 Watermaster Perchlorate Issues meeting, you and I each received a copy of a Stetson map showing perchlorate sampling and analysis data and locations from various wells in the San Gabriel Basin. This map shows numerous "hits" of perchlorate scattered throughout the region and remote from the BPOU plume. Two of these wells (City of Covina No 2 and Valencia Heights Water Company No. 4) contain perchlorate in excess of the provisional DHS action level. This

map clearly demonstrates that other perchlorate PRPs may exist both within and outside of the BPOU boundaries. What is EPA's intent as to evaluating the basin and particularly the BPOU for other perchlorate PRPs?

Very truly yours,

Ranna Lee

For Donald E. Vanderkar, Director
Environmental Restoration Programs

cc:

John Catts

BPOU Steering Committee



92-204-139-22

10395 Old Placerville Road Sacramento, CA 95827 (916)362-5332

LOCKHEED BEAUMONT NO. 1 TREATABILITY STUDY



Prepared for:

Lockheed Corporation 4500 Park Granada Boulevard Calabasas, CA 91302

Prepared by:

Radian Corporation 10395 Old Placerville Road Sacramento, CA 95827

February 1992

TABLE OF CONTENTS

Sect	ion		Page
	EXE	ECUTIVE SUMMARY	. E-1
1.0	INT	RODUCTION	. 1-1
	1.1	Background	
		1.1.1 One-Time Burial of Low-Level Radioactive Waste	
		1.1.2 Permitted Landfill	
		1.1.3 Burn Pit and Rocket Motor Production Areas	
	1.2	Design of the Treatability Study	
	1.3	Layout of Treatment Systems	. 1-9
2.0	CHA	ARACTERIZATION OF SITE CONTAMINATION	. 2-1
	2.1	Summary of Field Methods	2-7
	2.2	Geologic Conditions	
		2.2.1 Mt. Eden Formation	
		2.2.2 Granitic Formation	
	2.3	Vadose Zone Contamination	
	2.4	Groundwater Contamination	_
		2.4.1 Occurrence and Movement	_
		2.4.2 Groundwater Quality	
3.0	VAP	OR RECOVERY AND AQUIFER TESTING	. 3-1
	3.1	Vapor Recovery Tests	. 3-1
		3.1.1 Vapor Well Design and Layout	
		3.1.2 Data Needs for Design of a Full-Scale Vapor	
		Recovery System	. 3-6
		3.1.3 Vapor Recovery Test Program	3-8
		3.1.4 Sampling and Analytical Procedures	3-10
		3.1.5 Vapor Recovery Test Results	3-11
		3.1.6 Relation of Vapor Recovery Results to Final Design	2 22
	3.2	and Costs	
	3.2	3.2.1 Aquifer Test Design and Layout	
		3.2.2 Data Needs for Design of a Full-Scale Groundwater	3-33
		Recovery System	2.36
		3.2.3 Aquifer Test Layout	
		3.2.4 Aquifer Test Methods	
		3.2.5 Aquifer Test Results	
		3.2.6 Relation of Aquifer Tests to Final Design and Costs	J-44

TABLE OF CONTENTS (Continued)

Secti	ion		Page
4.0	CAF	RBON TREATABILITY OF SOIL VAPORS FROM THE VAPOR	
	REC	COVERY UNIT	. 4-1
	4.1	Activated Carbon Process Description	. 4-2
		4.1.1 Test Equipment Configuration	
		4.1.2 Activated Carbon Theory	
	4.2	Data Needs for Design of a Full-Scale Carbon System	. 4-6
	4.3	Carbon Test Program	
		4.3.1 Sampling and Analytical Procedures	
		4.3.2 Field Test Program	
	4.4	Activated Carbon Results	
		4.4.1 Test 1 - Carbon Adsorption Efficiency	
		4.4.2 Test 3 - Carbon Adsorption Efficiency	
		4.4.3 Test 4 - Carbon Adsorption Efficiency	
		4.4.4 Comparison of Test Results with Vendor Predictions	
		4.4.5 Carbon Loading Rates	
		4.4.6 Condensate Water	. 4-19
	4.5	Implication of Results on Costs	. 4-20
5.0	ULT	RAVIOLET LIGHT/HYDROGEN PEROXIDE/OZONE	
	GRO	DUNDWATER TREATMENT TEST PROGRAM	. 5-1
	5.1	UV Oxidation Process Description	. 5-1
		5.1.1 Equipment Configuration	
		5.1.2 UV Oxidation Theory	
	5.2	Data Needs for Design of a Full-Scale UV Oxidation Groundwater	
		Treatment System	5-9
	5.3	UV Oxidation Test Program	
		5.3.1 Sampling and Analytical Procedures	
		5.3.2 Field Test Program	
	5.4	UV Oxidation Results	
		5.4.1 Equipment Blank Check	
		5.4.2 Control Runs	
		5.4.3 Removal of VOCs by UV Oxidation	
		5.4.4 Optimum Operating Conditions	
		5.4.5 Discussion of Results for Intermediates/Byproducts	
		5.4.6 Analytical Results for Other Parameters	
		5.4.7 Field Operational Experiences and Problems	
	5.5	Implications of Results on Costs	
	J.J	mhuanam or soonm on com	J-JJ

TABLE OF CONTENTS (Continued)

Sect	ion	Pag	£
6.0	ULT	RAVIOLET LIGHT/HYDROGEN PEROXIDE/OZONE	
	COI	REATMENT TEST PROGRAM 6-	1
	6.1	UV Oxidation Cotreatment Process Description 6-	1
	6.2	Data Needs for the Design of a Full-Scale UV Oxidation	
		Cotreatment System 6-	
	6.3	UV Oxidation Test Program 6-	
		6.3.1 Sampling and Analytical Procedures 6-	
		6.3.2 Field Test Program 6-	7
	6.4	UV Oxidation Cotreatment Results	8
		System 6-1	0
		6.4.2 Performance Data for Cotreatment Subsystem - UV	
		Reactor 6-1	6
		6.4.3 Performance Data for the Cotreatment Subsystem -	
		D-TOX Unit	9
		6.4.4 Other Parameters in Groundwater 6-2	1
		6.4.5 Field Operational Experiences and Problems 6-2	3
	6.5	Implications of Results on Costs 6-24	1
7.0	AIR	STRIPPER/CARBON UNIT TESTING	i
	7.1	Air Stripping Process Description	
		7.1.1 Equipment Configuration	2
		7.1.2 Air Stripping Theory	
	7.2	Data Needs for Design of a Full-Scale Air Stripper 7-6	5
	7.3	Air Stripper Test Program 7-9)
		7.3.1 Sampling and Analytical Procedures	
		7.3.2 Field Test Program	l
	7.4	Air Stripper Results 7-16	5
		7.4.1 Equipment Blank Run	5
		7.4.2 Removal of VOCs by Air Stripping	ţ
		7.4.3 Mass Transfer Results	ļ
		7.4.4 Full-Scale Design Considerations)
		7.4.5 Inorganic Analytical Results)
	7.5	Implications of Results on Costs	

TABLE OF CONTENTS (Continued)

<u>Secti</u>	<u>Section</u>		
8.0	ION	EXCHANGE TREATMENT	. 8-1
	8.1	Ion Exchange Process Description	
		8.1.1 Equipment Configuration	
	0.0	8.1.2 Ion Exchange Theory	
	8.2 8.3	Data Needs for Design of a Full-Scale Ion Exchange Unit	
	8.3	Ion Exchange Test Program	
		8.3.2 Field Test Program	
	8.4	Ion Exchange Results	
	.	8.4.1 Inorganic Analytical Results	
		8.4.2 Organic Analytical Results	. 8-14
		8.4.3 Resin Breakthrough Determination	. 8-14
		8.4.4 Resin Regeneration/Degradation	. 8-15
	8.5	Implications of Results on Cost	. 8-17
9.0	TRE	ATED WATER INJECTION	. 9-1
	9.1	Injected Water Quality	. 9-1
	9.2	Injection Well Performance	. 9-1
	9.3	Implications for Final Design	. 9-3
10.0		L-SCALE DESIGN AND ASSOCIATED COSTSCONCLUSIONS	
	AND	RECOMMENDATIONS	. 10-1
11.0	REF	ERENCES	. 11-1
	APP	ENDIX A - WELL DATA	
	APP	ENDIX B - QA/QC	
	APPI	ENDIX C - ANALYTICAL DATA	

LIST OF TABLES

Table	. I	Page
S-1 S-2	Summary of Test Data for Treatability Study	
2-1 2-2	Analytical Results for Soil Samples Collected in the Burn Pit Area	
3-1 3-2 3-3 3-4	Vapor Well Construction Summary Vapor Recovery Test Data Maximum Vacuum Versus Distance for Vapor Recovery Tests Aquifer Test Summary	3-9 3-16
4-1 4-2	Carbon Study Test Data and Influent Concentrations	
5-1 5-2 5-3	Specifications for the Ultrox® Pilot System	5-13 5-18
5-4 5-5 5-6 5-7 5-8	Performance Data for Selected VOCs in Groundwater	5-21 5-25
J-0	Treatability Study	5-29
6-1 6-2	Cotreatment Test Plan	
6-3 6-4	Performance Data for Selected VOCs in the UV Oxidation System	5-14
7-1 7-2 7-3 7-4 7-5	Equipment List for Air Stripper	7-6 7-9 -11
7-6 7-7	Contaminants	-14

LIST OF TABLES (Continued)

Table	r en la companya de	age
7-8	Total VOC Contaminant Loading and Mass Balance for Each Test	
	Run of the Pilot-Scale Air Stripper Study	/-19
7-9	Trichloroethene Concentrations and Removal Efficiency for Each	
	Test Run of the Pilot-Scale Air Stripping Study	/-21
7-10	1,1-Dichloroethene Concentrations and Removal Efficiency for Each	
	Test Run of the Pilot-Scale Air Stripping Study	/-22
7-11	1,1,1-Trichloroethane Concentrations and Removal Efficiency for	_
	Each Test Run of the Pilot-Scale Air Stripping Study	/-23
7-12	Experimental and Theoretical TCE Mass Transfer Coefficient	
	Values	1-26
7-13	Summary of Inorganic Results for the Air Stripping Unit	/-31
8-1	Ion Exchange/Final Effluent Treatment Objectives	8-2
8-2	Summary of Influent and Effluent Results for the Ion Exchange Unit 8	-11
8-3	Analytical Results of the Chloride Form of the Anion Resin	-16
10-1	Initial Parameters for Preliminary Design Basis	0-3
10-2	Soil Vapor Carbon Treatment System - Preliminary Design	
10-3	Ultraviolet/Ozone/Hydrogen Peroxide Soil and Groundwater	
	Cotreatment System - Preliminary Design	0-5
10-4	Ultraviolet/Ozone/Hydrogen Peroxide Groundwater Treatment	
	System - Preliminary Design	0-6
10-5	Air Stripper Groundwater Treatment System - Preliminary Design 1	0-7
10-6	Ion-Exchange Groundwater Treatment - Preliminary Design	0-8
10-7	Order-of-Magnitude Full-Scale Treatment Cost Estimates	0-9

LIST OF FIGURES

Figur	Page Page
S-1	Lockheed Beaumont Site No. 1 Treatment Pilot Plant Process Flow Diagram E-2
1-1	Location of Lockheed Beaumont No. 1 and No. 2 Sites
1-2	Lockheed Beaumont No. 1 Facility
1-3	Lockheed Beaumont Site No. 1 Treatment Pilot Plant Process Flow Diagram
1-4	Layout of Vapor Monitoring and Recovery Wells
1-5	Location of Piping Network to Vapor and Groundwater
	Extraction, Treatment and Monitoring System
2-1	Lockheed Beaumont No. 1 Location of Wells and Piezometers 2-5
2-2	Lockheed Beaumont No. 1 Location of Wells and Borings in the
	Burn Pit Area
2-3	Lockheed Beaumont No. 1 Bottom of Quaternary Alluvium 2-9
2-4	Lockheed Beaumont No. 1 Total Volatile Organic Compound Soil
	Vapor Isopleths (From 1990 Study)
2-5	Lockheed Beaumont No. 1 Water Table Elevations, March 8, 1991 2-14
2-6	Lockheed Beaumont No. 1 Nitrate Concentrations in Shallow
2-7	Groundwater (late 1990)
Z- /	Lockheed Beaumont No. 1 Total 8010 Concentrations in Shallow Groundwater (Fall 1991)
2-8	Lockheed Beaumont No. 1 TCE Concentrations in Shallow Groundwater
2-0	(Fall 1991)2-21
2-9	Lockheed Beaumont No. 1 Perchlorate Concentrations in Shallow
2-9	Groundwater (Spring 1991)
	Croundwater (oping 1771)
3-1	Layout of Vapor Monitoring and Recovery Wells
3-2	Cross Section A-A' of VRW-3 and Associated Vapor
	Monitoring Wells 3-4
3-3	Cross Section B-B' of VRW-1 and VRW-2 and Associated Vapor
	Monitoring Wells
3-4	Vapor Recovery Test 1, VRW-2 Influent Concentration versus Time 3-12
3-5	Vapor Recovery Test 1, VRW-2 Monitoring Well Vacuum Distributions 3-15
3-6	Vapor Recovery Test 1, Vacuum versus Distance from VRW-2 3-17
3-7	Vapor Recovery Test 3, VRW-1 Influent Concentration versus Time 3-21
3-8	Vapor Recovery Test 3, VRW-1 Monitoring Well Vacuum Distributions 3-23
3-9	Vapor Recovery Test 3, Vacuum versus Distance from VRW-1 3-24
3-10	Vapor Recovery Test 4, VRW-2 Influent Concentration versus Time 3-26
3-11	VMW-14 Concentration versus Time

LIST OF FIGURES (Continued)

	Page
VMW-11 Concentration versus Time	. 3-29
Process Flow Diagram of Vapor Recovery and Carbon Adsorption	
Treatment Unit	. 4-3
Vapor Recovery Test 1-VRW-2 Effluent Concentration versus Time	. 4-12
Vapor Recovery Test 3-VRW-1 Effluent Concentration versus Time	. 4-13
Vapor Recovery Test 4-VRW-2 Effluent Concentration versus Time	. 4-14
Diagram of Ultraviolet/Hydrogen Peroxide/Ozone Pilot Treatment	
	. 5-3
Vapor for Each Run of the UV Oxidation Unit	. 5-16
Diagram of Ultraviolet Light/Hydrogen Peroxide/Ozone Cotreatment	
	. 6-2
Schematic of Sampling Locations (Cotreatment)	. 6-6
Total VOC Concentration Profiles for Groundwater and Vapor in the	
UV Oxidation Cotreatment System	. 6-17
Pilot Air Stripper Unit - Process Flow Diagram	. 7-3
Ion Exchange System	. 8-3
	VMW-11 Concentration versus Time Vapor Recovery Test 4, VRW-2 Vacuum Distribution Vacuum versus Distance from VRW-1 Process Flow Diagram of Vapor Recovery and Carbon Adsorption Treatment Unit Vapor Phase Adsorption Isotherms Vapor Recovery Test 1VRW-2 Effluent Concentration versus Time Vapor Recovery Test 3VRW-1 Effluent Concentration versus Time Vapor Recovery Test 4VRW-2 Effluent Concentration versus Time Diagram of Ultraviolet/Hydrogen Peroxide/Ozone Pilot Treatment System Schematic of Sampling Locations (Groundwater Treatment) Total VOC Concentration Profiles in Groundwater and Effluent Vapor for Each Run of the UV Oxidation Unit Diagram of Ultraviolet Light/Hydrogen Peroxide/Ozone Cotreatment System Schematic of Sampling Locations (Cotreatment)



EXECUTIVE SUMMARY

Radian Corporation has been retained by Lockheed Corporation to identify potential sources of surface and subsurface contamination and to prepare a remediation plan for a former Lockheed Propulsion Company test facility (Site No. 1) near Beaumont, California. Previous investigations have identified a soil vapor plume, originating from former burn pits, which contains chlorinated volatile organic contaminants (VOCs), primarily 1,1-dichloroethene (1,1-DCE), trichloroethene (TCE), and 1,1,1-trichloroethane (1,1,1-TCA). A narrow groundwater plume containing these contaminants in concentrations above state and federal Primary Maximum Contaminant Levels is present in the alluvial aquifer below the soil vapor plume. The groundwater plume originates and is widest at the burn pit and rocket motor production areas, and extends approximately 2 miles downgradient to the west. The same contaminants are also found in lesser concentrations in the upper, weathered portion of the underlying Mt. Eden Formation.

This report presents the test results of the treatability study conducted to investigate the subsurface characteristics during groundwater and soil vapor extraction, and to compare the effectiveness of vapor and groundwater treatment technologies. The objectives of the subsurface evaluation were to determine:

- The actual concentrations of contaminants in the soil vapor and groundwater at different locations during extraction;
- The pumping characteristics of the porous media in the subsurface that contain contaminated vapors and groundwater; and
- The rate at which soil vapor and groundwater can be extracted.

To provide technology-based engineering data, five technologies to treat the contaminated soil vapor and groundwater were evaluated and compared, as shown in Figure S-1 and summarized in Table S-1. Soil vapors contaminated with chlorinated VOCs


the groundwater. Figure 2-8 presents a contour map of TCE concentrations in groundwater. The highest contaminant concentrations are found in water table wells MW-24 and MW-26 drilled directly beneath the burn pits. The contaminants with the highest concentrations in these wells are TCE at 740 μ g/L (MW-24), 1,1-DCE at 740 μ g/L (MW-24), and 1,1,1-TCA at 140 μ g/L (MW-26). These levels are higher than the PMCL levels for 1,1-DCE (6 μ g/L) and TCE (5 μ g/L), but less than the PMCL for 1,1,1-TCA (200 μ g/L). Figure 2-7 combines these results and presents a map of the total amount of contaminants present. Immiscible phase product or contamination was not observed during the drilling of these two wells.

In order to evaluate if contamination has migrated into the Mt. Eden Formation, deeper wells MW-31 (in the burn pits), MW-3, and MW-32 (downgradient) were drilled to depths of 85 to 140 feet below the water table. Water samples from these three deep wells did not contain detectable concentrations of organic compounds, indicating that contamination has not migrated to the deeper unweathered portion of the Mt. Eden Formation.

Data to evaluate the vertical distribution of contaminants were obtained from MW-30 and MW-21. MW-30, screened from about 30 to 65 feet below the water table, was pumped during the treatability study to supply water for the pilot treatment program. Chemical analysis of the discharge water indicated that the water from this well was much less contaminated than water from MW-21, which is approximately 22 feet from MW-30 and screened from 0 to 29 feet below the water table. The rapid decrease in contaminant concentrations with depth observed in these wells supports the conclusion that the contaminant plume is relatively thin. Analytical data from these and other wells screened at various depths below the water table indicate that the contaminant plume is probably less than 40 or 50 feet thick.

In addition to the presence of nitrates and chlorinated organics, perchlorates were detected in groundwater beneath the burn pit area. Ammonium perchlorate was used at the site as one of the ingredients in the manufacture of rocket fuels. Concentrations of

perchlorate in the groundwater ranged from less than 0.01 to 9.1 mg/L. A perchlorate contour map, shown on Figure 2-9, indicates that the perchlorate contamination most likely originates at the burn pit and migrates downgradient in a pattern similar to that of the other contaminants.



LOCKS PERCH 02/07/92